

SLCS -067-S/ 04.03.2019

CLARIFICATIONS

regarding the procedure for contracting *Infrastructure fitting - equipment and implementation services and Furniture and fitting* within the project FAIT – *Fight against illegal trade*

No. crt.	Questions/observations	Answers
1.	<p>During the site-survey it was noticed that the 70 telephony ports cabled in the telephony switch on the 9th floor need to be cabled in the new rack on the 10th floor.</p> <p>Therefore, please confirm that the offer must include this copper intercom consisting of: interior cable 1x100 pairs or 2x50 pairs, 80m length; 4 telephony patch panels of 50 ports Cat.3; 70 patch cords Cat.3.</p>	<p>We confirm that the offer must include the copper intercom consisting of: interior cable 1x100 pairs or 2x50 pairs, 80m length; 4 telephony patch panels of 50 ports Cat.3; 70 patch cords Cat.3.</p>
2.	<p>During the site-survey, it was considered to be excessive the initial request of 3 Schuko sockets and 2 USB ports per each pop-up and workstation in the OCU Room. Therefore, it was proposed pop-ups with 1 Schuko socket and 2 USB ports each.</p>	<p>We confirm that we accept pop-ups with 1 Schuko socket and 2 USB ports each.</p>
3.	<p>During the site-survey it was observed that the already existing glass doors in the area of OCU can be reused.</p>	<p>The applicant has also the option to re-use the doors and upgrade them with the requested lock system.</p>